

TOWN OF HOPKINTON

**INVITATION FOR BIDS**

Sealed proposals will be received by the Town of Hopkinton, 330 Main Street, Hopkinton, NH 03229 until **2:00 PM, Thursday, May 3, 2012** for the following project:

HOPKINTON  
2012-Paving

**THIS PROJECT INVOLVES PAVING, SHIMMING AND OVERLAY OF SEVERAL TOWN ROADS**

Bidders should act promptly and submit all questions concerning the project to Highway Superintendent John Thayer at (603) 746-5118, and questions about the bidding process to Neal Cass, Town Administrator, (603) 746-2892, at least five (5) days prior to the date set for the bid opening.

Plans and specifications may be seen at the Town Hall between the hours of 8 AM and 4:30 PM Monday through Thursday and 8 AM to noon on Friday.

**Specifications and proposal forms, FOR BIDDING PURPOSES, shall only be obtained at the HOPKINTON TOWN HALL, 330 MAIN STREET.**

Bids SHALL BE SUBMITTED IN A SEALED ENVELOPE MARKED "HOPKINTON PAVING 2012" and be received by the Town no later than specified above, at which time they will be publically opened and read aloud.

Bidders must be a prequalified contractor for paving by NHDOT.

The successful bidder will be required to furnish a contract performance bond or acceptable surety in the amount of one hundred (100) percent of their bid. The successful bidder will also be required to produce a certificate evidencing liability insurance coverage of at least one million dollars (\$1,000,000) in the aggregate prior to award of contract.

The *HOPKINTON SELECTMEN* reserve the right to waive any informality and to reject any and all proposals.

April 11, 2012

*TOWN OF HOPKINTON, NH*  
**INFORMATION REPORT**

**PROJECT:** HOPKINTON PAVING 2012  
PAVING, SHIMMING AND OVERLAY

**DATE BIDS OPEN:** Thursday, May 3, 2012 2:00 p.m.

**SCOPE OF WORK:** HOT BITUMINOUS PAVEMENT CONSTRUCTION

**COMPLETION DATE:** OCTOBER 1, 2012

**CONSTRUCTION SURETY:** 100% OF BID AWARD

**TOWN FUNDING:** 100%

**ESTIMATED QUANTITIES**

**ITEM 403.11 ONE (1) INCH HOT BITUMINOUS PAVEMENT, MACHINE METHOD**

<u>LOCATION</u>	<u>LENGTH</u>	<u>WIDTH</u>	<u>EST. QUANTITY</u>
Dustin Road (overlay)	6,000 FT	20 FT	750 Tons
Spring Street (overlay)	3,500 FT	20 FT	440 Tons
<b>TOTAL</b>	<b>9,500 FT</b>		<b>1,190 Tons</b>

**ITEM 403.11 TWO (2) INCH HOT BITUMINOUS PAVEMENT, MACHINE METHOD**

<u>LOCATION</u>	<u>LENGTH</u>	<u>WIDTH</u>	<u>EST. QUANTITY</u>
Spring Street (new construction)	100 FT	20 FT	25 Tons
<b>TOTAL</b>	<b>100 FT</b>		<b>25 Tons</b>

**ITEM 411.1 HOT BITUMINOUS CONCRETE LEVELING COURSE;**  
**ITEM 403.11 ONE (1) INCH HOT BITUMINOUS PAVEMENT, MACHINE METHOD; USING HOT**  
**SPRAYED TACK SEALANT AND RUBBER TIRED ROLLER, ALL JOINTS WILL BE TRIMMED**  
**TO FORM BUTT JOINTS.**

<u>LOCATION</u>	<u>LENGTH</u>	<u>WIDTH</u>	<u>EST. QUANTITY</u>
Emerson Hill Road	1,800 Ft	21 FT	415 Tons
Amesbury Park Road	3,800 FT	18 FT	640 Tons
Pinewood Drive	3,300 FT	20 FT	620 Tons
Hardy Lane	500 FT	20 FT	63 Tons
Woodland Drive	2,000 FT	20 FT	360 Tons
Transfer Station			750 Tons
<b>TOTAL</b>	<b>11,400 FT</b>		<b>2,848 TONS</b>

**ALL MATERIALS AND WORKMANSHIP WILL BE IN ACCORDANCE WITH NHDOT STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, 2006.**

TOWN OF HOPKINTON, NH  
HOT BITUMINOUS PAVING, SHIMMING AND OVERLAY  
**Hopkinton Paving 2012**  
BID PROPOSAL

ITEM	DESCRIPTION	UNIT	QUANTITY	PRICE	TOTAL
403.11	ONE (1) INCH HOT BITUMINOUS PAVEMENT MACHING METHOD	TON	1,190	\$	\$
403.11	TWO (2) INCH HOT BITUMINOUS PAVEMENT MACHINE METHOD	TON	25	\$	\$
411.1 403.11	HOT BITUMINOUS LEVELING COURSE, ONE (1) INCH HOT BITUMINOUS PAVEMENT, TACK COAT, RUBBER TIRED ROLLER, JOINTS TRIMMED	TON	2,848	\$	\$

BID TOTAL    \$ \_\_\_\_\_

BID TOTAL IN WORDS: \_\_\_\_\_

ALL MATERIALS AND WORKMANSHIP WILL BE IN ACCORDANCE WITH NHDOT STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, 2006.

**UNIT PRICES INCLUDE ALL NECESSARY WORK REQUIRED TO PROVIDE A COMPLETED PROJECT. TRAFFIC CONTROL, ROAD SWEEPING AND MOBILIZATION ARE SUBSIDIARY.**

SIGNING WILL BE IN ACCORDANCE WITH M.U.T.C.D. STANDARDS.

**IT IS ANTICIPATED THAT ALL RESURFACING PROJECTS WILL BE READY FOR PAVING BY JULY 9, 2012.**

**THE FINAL COMPLETION DATE IS SEPTMEBER 28, 2012. LIQUIDATED DAMAGES ARE \$150 PER CALANDAR DAY EXCEEDING THE COMPLETION DATE.**

THE TOWN RESERVES THE RIGHT, WITH NO CHANGES IN UNIT PRICING, TO ADD OR ELIMINATE PORTIONS OF THE WORK. **THE SELECTMEN RESERVE THE RIGHT TO WAIVE ANY INFORMALITY AND TO REJECT ANY AND ALL PROPOSALS.**

\_\_\_\_\_  
SIGNED

\_\_\_\_\_  
PRINTED/TYPED

\_\_\_\_\_  
FIRM NAME

\_\_\_\_\_  
ADDRESS

\_\_\_\_\_  
CITY/TOWN

\_\_\_\_\_  
STATE

\_\_\_\_\_  
ZIP CODE